

Replies to Query

“Landscaping and Horticulture Works at 5MW Solar Power Plant with One Year Maintenance” at DMICDC Neemrana Solar Power Company Limited, Plot No.-80 & 81, Japanese Zone, RIICO Industrial Area, Neemrana, Distt. – Alwar, Rajasthan-301705

Sl. No.	RFP reference	Query related to	Query	Response to the query
1	Annexure-“C” BOQ Part A1: Horticulture Works Point 4	Plantation of Grass	Under the solar panels it is not practical & feasible to grow & maintain grass. Can we plant Ground Cover under it? There is no such mention in your tender.	As per the discussions with various horticulture experts, it is learnt that growing grass under the solar panels is both feasible and same can also be maintained. Plantation for ground cover by using plants like wedelia or equivalent instead of grass is permitted at no additional cost to the company.
2	Technical Requirement Point No. 44	Water source/water irrigation system will be provided by the client.	How much water will be provided by you for regular maintenance?	For regular maintenance, client will provide adequate water. At present, the water supply from RIICO is being used with a storage tank of 2 lakh litre.
3	Technical Requirement Point No. 44	Water source/water irrigation system will be provided by the client.	Which work will be completed first, laying of irrigation system or Horticulture?	Installation of irrigation system work will be completed first. During the meantime following works may be completed by the selected agency: <ol style="list-style-type: none"> 1. Rough dressing the trenched ground including breaking clods. 2. Fine Dressing of ground 3. Ground preparation except using manure and fertilizer. 4. Preparation of beds for hedge, shrubs and tress. 5. Plantation of 600 Nos. Bouganvillia (3'-4') Multi Colour (Named Variety), 50 No.s Phoenix palm (3'ht), 100 No.s Calendra (3'-4'), 100 No.s Cassia Gluca

				(3'-4'), 50 No.s Bottle brush (7'-8' ht), 100 No.s General Plant (Ashok Pendula) and Enermi (1') for hedge.
4	Technical Requirement Point No. 44	Water source/water irrigation system will be provided by the client.	If Horticulture is to be completed first then, who will do the do the trenching, refilling & Re-grassing in the lawn area?	Not Applicable as Same has described in Sr. No. 3.